

Section 01572

POLLUTION SOURCE CONTROLS ON CONSTRUCTION PROJECTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Description of erosion, sediment control and other control-related practices utilized during construction activities.

1.02 UNIT PRICES

- A. Unless indicated in Unit Price Schedule as a pay item, no separate payment shall be made for Work performed under this Section. Include cost of Work performed under this Section in pay items of which this Work is a component.

1.03 REFERENCE STANDARDS

- A. ASTM D 4632 - Standard Test Method for Grab Breaking Load and Elongation of Geotextiles.
- B. Storm Water Quality Management Guidance Manual prepared by City of Tomball, Harris County and Harris County Flood Control District.

1.04 SUBMITTALS

- A. Submit manufacturer's catalog sheets and other product data on dispensing equipment, pump, and aboveground fuel storage tanks, indicating capacity and dimensions of tank.
- B. Submit drawings to show location of tank protection area and driveway. Indicate nearest inlet or channelized flow area. Clearly dimension distances and measurements.
- C. Submit list of spill containment equipment, and quantities thereof, located at fueling area.
- D. Submit manufacturer's catalog sheets and other product data on geotextile fabric.

1.05 QUALITY ASSURANCE

- A. Person conducting visual examination for pollutant shall be fully knowledgeable about the NPDES Construction General Permit, detecting sources of storm water contaminants, inspection of aboveground storage tank and appurtenances for leakage, and the day-to-day operations that may cause unexpected pollutant releases.

PART 2 PRODUCTS

2.01 ABOVEGROUND STORAGE TANK

- A. Tank Assembly: Must be listed with UL 1709 and UL 2085.
- B. Inner Steel Storage Tank: Follow UL 142, with minimum thickness of 1/8-inch welded construction.
- C. Tank Encasement: Either concrete or steel to provide minimum of 110 percent containment of inner tank capacity. Provide 5-gallon overspill containment pan for tank refueling.
- D. Dispenser Pump: For submersible pump, UL listed emergency shut-off valve to be installed at each dispenser. For suction pump, UL listed vacuum-activated shut-off valve, with shear section, is to be installed at each dispenser. Fuel may not be dispensed from tank by gravity flow or by pressurization of tank. Means must be provided to prevent release of fuel by siphon flow.
- E. Representative Manufacturers: Convault, Fireguard, Ecovault, SuperVault, or equal.

2.02 CONCRETE

- A. Provide concrete with minimum strength of 4,000 psi at 28 days.

2.03 AGGREGATES

- A. Coarse aggregate shall consist of crushed stone, gravel, crushed blast furnace slag, or combination of these materials. Aggregate shall be composed of clean, hard, durable materials, free from adherent coatings, salt, alkali, dirt, clay, loam, shale, soft or flaky materials, or organic and injurious matter.
- B. Coarse aggregates shall conform to following gradation requirements.

Sieve Size (Square Mesh)	Percent Retained (By Weight)
2-1/2"	0
2"	0 - 20
1-1/2"	15 - 50
3/4"	60 - 80
No. 4	95 - 100

2.04 GEOTEXTILE FABRIC

- A. Provide woven or non-woven geotextile filter fabric made of either polypropylene, polyethylene, ethylene, or polyamide material in continuous rolls of longest practical length.
- B. Geotextile fabric shall have a grab strength of 270 psi in any principal direction (ASTM D4632), Mullen burst strength exceeding 200 psi (ASTM D-3786) and equivalent opening size between 50 and 70.
- C. Filter fabric material shall contain ultraviolet inhibitors and stabilizers to provide minimum of 6 months of expected usable construction life at a temperature range of 0 degrees F to 120 degrees F.
- D. Representative Manufacturers: Mirafi, Inc., Synthetic Industries, or equal.

### PART 3 EXECUTION

#### 3.01 PREPARATION AND INSTALLATION

- A. No clearing and grubbing or rough cutting permitted until erosion and sediment control systems are in place, other than site Work specifically directed by City Engineer to allow soil testing and surveying.
- B. Prohibit equipment and vehicles from maneuvering on areas outside of dedicated rights-of-way and easements for construction. Immediately repair damage caused by construction traffic to erosion and sediment control systems.
- C. Maintain existing erosion and sediment control systems located within project site until acceptance of Project or until directed by City Engineer to remove and discard existing system.
- D. Regularly inspects and repairs or replaces damaged components of erosion and sediment control systems as specified in this Section. Unless otherwise directed, maintain erosion and sediment control systems until project area stabilization is accepted by City. Remove erosion and sediment control systems promptly when directed by City Engineer. Discard removed materials off site.
- E. Remove and dispose sediment deposits at designated spoil site for Project. If a project spoil site is not designated on Drawings, dispose of sediment off site at location not in or adjacent to stream or flood plain. Assume responsibility for off-site disposal. Spread sediment evenly throughout site, compacted and stabilized. Prevent sediment from flushing into a stream or drainage way. If sediment has been contaminated, dispose of in accordance with existing federal, state, and local rules and regulations.
- F. Assume responsibility for collecting, storing, hauling, and disposing of spoil, silt, and waste materials as specified in this or other Specifications and in compliance with applicable federal, state, and local rules and regulations.

- G. Employ protective measures to avoid damage to existing trees to be retained on project site. Conduct construction operations under this Contract in conformance with erosion control practices described in Drawings and this Specification.
- H. Prepare spill response and containment procedures to be implemented in event of significant materials spill. Significant materials include but are not limited to: raw materials; fuels; materials such as solvent, detergents, and plastic pellets; finished materials such as metallic products; raw materials used in food processing or production; hazardous substances designated under section 101(14) of CERCLA; chemical required to be reported pursuant to Section 313 of Title III of SARA; fertilizers; pesticides, and waste products such as slag, ashes and sludge that have potential to be released with storm water discharges. Spill containment procedures shall be kept on-site or in construction field office.
- I. Spill containment equipment appropriate to size of operation is to be located in close proximity of fueling area. Such equipment includes, but not limited to, suitable waste containers for significant materials, drip pans, booms, inlet covers, or absorbent.
- J. Properly label significant materials or waste containers used for construction activities and stored on-site overnight.
- K. Install, maintain, and inspect erosion, sediment control measures and practices as specified in Drawings and in this or other Specifications.

3.02 TOPSOIL PLACEMENT FOR EROSION AND SEDIMENT CONTROL SYSTEMS

- A. When topsoil is specified as a component of another Specification, conduct erosion control practices described in this Specification during topsoil placement operations.
  - 1. When placing topsoil, maintain erosion and sediment control systems consisting of swales, grade stabilization structures, berms, dikes, waterways, and sediment basins.
  - 2. Maintain grades, which have been previously established on areas to receive topsoil.
  - 3. After areas to receive topsoil have been brought to grade, and immediately prior to dumping and spreading topsoil, loosen sub grade by discing or by scarifying to a depth of at least 2 inches to permit bonding of topsoil to subsoil. Compact by passing bulldozer up and down slope, tracking over entire surface area of slope to create horizontal erosion control slots.
  - 4. No sod or seed shall be placed on soil, which has been treated with soil sterilants until sufficient time has elapsed to permit dissipation of toxic materials.

3.03 DUST CONTROL

- A. Implement dust control methods to control dust creation and movement on construction sites and roads and to prevent airborne sediment from reaching receiving streams or storm water conveyance systems, to reduce on-site and off-site damage, to prevent health hazards, and to improve traffic safety.
- B. Control blowing dust by using one or more of following methods:
  - 1. Mulches bound with chemical binders such as Carasol, Terratack, or equal.
  - 2. Temporary vegetative cover.
  - 3. Spray-on adhesives on mineral soils when not used by traffic.
  - 4. Tillage to roughen surface and bring clods to surface.
  - 5. Irrigation by water sprinkling.
  - 6. Barriers using solid board fences, snow fences, burlap fences, crate walls, bales of hay, or similar materials.
- C. Implement dust control methods immediately whenever dust can be observed blowing on project site.

3.04 KEEPING STREETS CLEAN

- A. Keep streets clean of construction debris and mud carried by construction vehicles and equipment. If necessary, install stabilized construction exits at construction, staging, storage, and disposal areas. Vehicle/equipment wash area (stabilized with coarse aggregate) may be installed adjacent to stabilized construction exit, as needed. Release wash water into a drainage swale or inlet protected by erosion and sediment control measures. Construction exit and wash areas are specified in Section 01575 - Stabilized Construction Exit.
- B. In addition to stabilized construction exits, shovel or sweep pavement to extent necessary to keep street clean. Water hosing or sweeping of debris and mud off of street into adjacent areas is not allowed.

3.05 EQUIPMENT MAINTENANCE AND REPAIR

- A. Confine maintenance and repair of construction machinery and equipment to areas specifically designated for that purpose. Locate areas so that oils, gasoline, grease, solvents, and other potential pollutants cannot be washed directly into receiving streams or storm water conveyance systems. Provide these areas with adequate waste disposal receptacles for liquid as well as solid waste. Clean and inspect maintenance areas daily.
- B. On construction site where designated equipment maintenance areas are not feasible, take precautions during each individual repair or maintenance operation to prevent potential

pollutants from washing into streams or conveyance systems. Provide temporary waste disposal receptacles.

3.06 WASTE COLLECTION AND DISPOSAL

- A. Formulate and implement a plan for collection and disposal of waste materials on construction site. In plan, designate locations for trash and waste receptacles and establish a collection schedule. Specify and carry out methods for ultimate disposal of waste in accordance with applicable local, state, and federal health and safety regulations. Make special provisions for collection and disposal of liquid wastes and toxic or hazardous materials.
- B. Keep receptacles and waste collection areas neat and orderly to extent possible. Waste shall not be allowed to overflow its container or accumulate from day-to-day. Locate trash collection points where they shall least likely be affected by concentrated storm water runoff.

3.07 WASHING AREAS

- A. Avoid washing concrete delivery trucks or dump trucks and other construction equipment at locations where runoff shall flow directly into a watercourse or storm water conveyance system. Designate special areas for washing vehicles. Locate these areas where wash water shall spread out and evaporate or infiltrate directly into ground, or where runoff can be collected in temporary holding or seepage basin. Beneath wash areas construct a gravel or rock base to minimize mud production.

3.08 STORAGE OF CONSTRUCTION MATERIALS AND CHEMICALS

- A. Isolate sites where chemicals, cements, solvents, paints, or other potential water pollutants are stored in areas where they shall not cause runoff pollution.
- B. Store toxic chemicals, materials, pesticides, paints, and acids in accordance with manufacturers' guidelines. Protect groundwater resources from leaching by placing a plastic mat, packed clay, tar paper, or other impervious materials on areas where toxic liquids are to be opened and stored.

3.09 DEMOLITION AREAS

- A. Demolition activities which create large amounts of dust with significant concentrations of heavy metals or other toxic pollutants shall use dust control techniques to limit transport of airborne pollutants. However, retain water or slurry used to control dust contaminated with heavy metals or toxic pollutants on site, and prevent runoff directly into watercourses or storm water conveyance systems. Carry out methods of ultimate disposal of these materials in accordance with applicable local, state, and federal health and safety regulations.

3.10 SANITARY FACILITIES

- A. Provide construction sites with adequate portable toilets for workers in accordance with Section 01504 - Temporary Facilities and Controls, and applicable health regulations.

3.11 PESTICIDES

- A. Use and store pesticides during construction in accordance with manufacturer's guidelines and with local, state, and federal regulations. Avoid overuse of pesticides, which could produce contaminated runoff. Take great care to prevent accidental spillage. Never wash pesticide containers in or near flowing streams or storm water conveyance systems.

3.12 CONSTRUCTION METHODS

- A. Provide fuel tank protection area and driveway as shown on Drawings.
- B. Do not locate fueling area in or near channelized flow area or close to storm sewer conveyance system. Provide sufficient space to allow installation of other erosion and sediment controls to protect those areas.
- C. Clear and grub fueling area to remove unsuitable materials. Place geotextile fabric as permeable separator to prevent mixing of coarse aggregate with underlying soil. Overlap fabric minimum of 6 inches. Place coarse aggregate on top of geotextile fabric to minimum depth of 8 inches.
- D. Grade protection area and driveway to provide sufficient drainage away from stabilized areas. Use sandbags, gravel, boards, or similar methods to prevent sediment from entering public right-of-way, receiving stream or storm water conveyance system. Provide driveway to fuel tank area with minimum width of 15 feet for one-way traffic and 30 feet for two-way traffic.
- E. Place aboveground storage tank on top of cast-in-place or pre-cast foundation. Base size and thickness of foundation on size and weight of tank to be used, with minimum thickness of 6 inches. Enclose concrete foundation by 5-inch by 5-inch concrete curb and extend minimum of 1 foot beyond tank and dispenser assemblies, so that leak and drip can be contained within concrete foundation.
- F. Slope concrete foundation minimum of 1 percent toward 6-inch wide by 12-inch long by 4-inch deep sump pit. Install minimum of 2-inch pipe inside sump pit with valve on outside of curb to allow draining of concrete foundation.
- G. Install portable concrete Jersey Barrier around concrete foundation. Provide minimum clearance of 2 feet from edge of foundation. In lieu of Jersey barrier, install 4-inch diameter steel pipe bollards around foundation. Bury bollards minimum of 3 feet deep, 3 feet above ground, and 4 feet on center, encased in 12-inch wide concrete foundation.

3.13 MAINTENANCE

- A. Inspections shall be conducted by designated health and safety officer qualified to conduct health and safety inspections.
- B. Inspect stabilized areas after every storm event and at least once a week. Provide periodic top dressing with additional coarse aggregate to maintain required depth. Repair and clean out damaged control measures used to trap sediment.
- C. Inspect fuel tank foundation's bermed area after every storm event and at least once a week. Visually examine storm water contained in tank's bermed foundation area for oil sheen or other obvious indicators of storm water pollution. Properly dispose of storm water when pollutant is present. Record visual examination of storm water discharge in Report noting date and time of examination, name of examiner, observations of water quality, and volume of storm water discharged from bermed area. Keep Report with other storm water pollution control inspection reports on site, in readily accessible location.

3.14 TEMPORARY FUELING AREA CLOSURE

- A. Dispose of temporary vehicle and equipment fueling area by removal of sediment and erosion controls properly off site. City Engineer will inspect topsoils in fueling area and immediate vicinity for evidence of fuel leaks. If City Engineer determines that sufficient pollutants have been released, remove soil and properly dispose off site. Other remediation methods may be required.

END OF SECTION