

Section 01581

EXCAVATION IN PUBLIC WAY PERMIT SIGNS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Project sign installation.
- B. Maintenance and removal of project sign.

1.02 MEASUREMENT AND PAYMENT

- A. Unit Prices: No separate payment will be made for Work included in this Section. Include cost of Excavation in Public Way Permit signs in overhead cost.
- B. Stipulated Price (Lump Sum). If Contract is Stipulated Price Contract, payment for Work in this Section is included in total Stipulated Price.

1.03 SYSTEM DESCRIPTION

- A. Sign Construction: Signs shall be constructed of new materials.
- B. Appearance: Signs shall be maintained to present clean and neat look throughout project duration.
- C. Sign Placement: Place signs at each street entrance to street cut excavation.

1.04 SUBMITTALS

- A. Submit shop drawings under provisions of Section 01330 - Submittal Procedures.
- B. Show content, layout, lettering style, lettering size and colors. Make sign and lettering to scale, clearly indicating condensed lettering, if used.

PART 2 PRODUCTS

2.01 SIGN LAYOUT

- A. Conform to Texas Manual on Traffic Control Devices. Minimum size: 36-inches by 36-inches.

- B. Lettering: Uppercase Helvetica Regular lettering.
- C. Composition: Include on sign copy of street cut permit, title a City of Tomball, contracting Department's name, address, and emergency telephone number and Contractor's name. City Engineer will provide Department name, address, and emergency telephone number for preparation of sign.

### PART 3 EXECUTION

#### 3.01 INSTALLATION

- A. Install project identification signs before commencement of excavation in pavement in Public Way.
- B. Position sign in such a manner as to be fully visible and readable to general public.
- C. Erect sign level and plumb.
- D. Erect sign so that top edge of sign is at nominal 8-feet above existing grade.

#### 3.02 MAINTENANCE AND REMOVAL

- A. Keep signs and supports clean. Repair deterioration and damage.
- B. Remove signs, framing, supports and foundations to depth of 2-feet upon completion of Project. Restore area to condition equal to or better than before construction.

END OF SECTION